

1-13-66

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-007-30230-0000

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 12 Twp. 31S Rge. 13 (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines C N/2 (250' east)
Lease Owner Chief Drilling Co., Inc.
Lease Name MADDIX "B" Well No. 1
Office Address Box 797 - Gt. Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/10 1966
Application for plugging filed 1/10 1966
Application for plugging approved 1/10 1966
Plugging commenced 1/10 1966
Plugging completed 1/10 1966
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving - Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3690 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	205	8-5/8"	205	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/4 sack hulls & wooden plug set @ 200'
Mixed 25 sacks cement through drill pipe
1/4 sack hulls & Wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Gt. Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CHIEF DRILLING CO., INC.

(Signature) V. Richard Hoover
Box 797 - Gt. Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 66

My commission expires Jan. 26, 1967
Carmen R. Cook, Notary Public.

15-067-36230-0000

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1966

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

MADDIX "B" #1
C N/2 (250' East)
Sec. 12-31S-13W
Barber County, Kansas

CONSERVATION DISTRICT
Barber County, Kansas

Contractor: Vaughan Drilling, Inc.

Commenced: 1-3-66
Completed: 1-10-66

Casing Record: 8-5/8" @ 205' w/150 sacks Sunset

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
			1689 Gr.
			1691 D.F.
			1693 K.B.
			<u>FORMATION TOPS</u>
Surface Clay & Red Shale	0	205	
Red Shale	205	595	
Shale & Lime	595	960	
Shale	960	1450	
Shale & Lime	1450	3320	
Lime	3320	3577	Heebner 3577 -1884
Shale & Lime	3577	3591	Toronto 3591 -1898
Lime	3591	3607	Douglas Shale 3607 -1914
Shale	3607	3635	Douglas Sand 3635 -1942
Sand	3635	3690	Total Depth 3690 -1997
Total Depth	3690		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C N/2 (250' East) Sec. 12-31S-13W, Barber County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 12th day of January, 1966.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.