

1-13-82

15-173-20453 0000

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sedgwick County, Sec. 6 Twp. 28S Rge. 1 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Oil Property Management, Inc.

Lease Name Schulte Well No. 1
Office Address 221 N. Main, Suite 200 - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-11-1982

Application for plugging filed 1-11-1982

Application for plugging approved 1-11-1982


Plugging commenced 1-11-1982

Plugging completed 1-11-1982

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled from 3690' T.D. to 340' with drilling mud, set plug, added 35 sx. cement, filled with drilling mud to 60' set plug, added 20 sx. cement, 5 sx. cement in rathole, 5 sx. cement in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1982

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R. R. A., Inc.
Address 510 Hardage Center - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. H. Peachee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me Gdd.

(Signature) W. H. Peachee

221 North Main, Suite 200
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1982

Doraine J. Starr
Notary Public.

My commission expires 10-1-85

DRILLER'S LOG

Oil Property Management, Inc.
Schulte No. 1
SW NW SE
Sec. 6-T28S-R1W
Sedgwick County, Kansas

15-173-28453-0000

Commenced: 12-30-81
Completed: 1-11-82

Surface Casing: 328' of 8-5/8"
Cemented W/200 sx., 3% CC, 2% gel

<u>Formation</u>	<u>Depth</u>
Surface	0 - 327
Shale & Sand	327 - 535
Shale & Lime	535 - 2400
Lime W/shale & sand	2400 - 2550
Shale & Lime	2550 - 2770
Lime W/shale	2770 - 2786
Kansas City Lime	2786 - 2883
Lime	2883 - 2930
Shale & Lime	2930 - 3038
Lime & Shale	3038 - 3345
Mississippi	3345 - 3542
Shale & Lime	3542 - 3690 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.


R. R. A., Inc.



By: Wm. A. McAdoo

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 11th day of January 1982.



Ada C. May
Notary Public Ada C. May