

1-25-45

15-173-06016-0000

STATE OF KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD

Give all information completely. Make Required Affidavit. Mail or Deliver Report to: Conservation Division, State Corporation Commission, 800 Bittling Building, Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

County Sec 8 Twp 28 Rge 1 (W)

Location as "NE 1/4 NW 1/4" or footage from lines NW 34 NW

Lease Owner William Stuckey

Lease Name L. F. George Well No.

Office Address.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Dec 1944 19

Application for plugging filed Dec 19 - 1944 19

Application for plugging approved Dec 19 - 1944 19

Plugging commenced Jan 1 1945 12-24 1944

Plugging completed 12-31 1944

Reason for abandonment of well or producing formation.

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dwight Lelley

Producing formation. Depth to top. Bottom. Total Depth of Well 36.78 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. All cells are empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

10 sack Plug in bottom of hole
10 " " in surface pipe at 145'
5 " " at top of surface pipe

PLUGGING FILE 8-28-R-1W BOOK PAGE 143 LINE 14

pd. 12/19/44

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to William Stuckey, 1735 East Main Wichita Kan.

STATE OF _____, COUNTY OF _____, ss. _____ (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William Stuckey

NOT NOTARIZED

Subscribed and Sworn to before me this 25th day of January 1945

My commission expires July 26th - 1947 Notary Public.

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas


15-173-50016-0000

Company - MODEL & ROLAND
 Farm - L.H.Gorges No. 1.

SEC. 8 T. 28 R. 1 W
 NW SW NW

Total Depth. 3678'
 Comm. 10-30-44 Comp. 12-4-44
 Shot or Treated.
 Contractor. R.C.Patton Co.
 Issued. 12-23-44

County. Sedgwick
 KANSAS



CASING:
 10" 145' Cem.
 5 1/2" 3678' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale	30
sand	120
shale	250
shale & shells	292
salt sheets	330
shale & lime shells	490
lime	700
shale	720
lime	845
shale & shells	875
shale & lime	1665
shale & shells	1740
lime	1880
shale & lime	1985
lime	2185
lime & shale	2380
lime	2520
shale stickey	2560
lime	2640
shale	2785
lime K.C.	2988
shale	3055
shale & lime	3330
shale	3356
sand	3386
lime Miss & chat	3434
lime	3472
lime cherty	3551
shale	3555
shale & lime	3674
Simpson	3678
Total Depth	

Fops:

K. C. 2780
 Miss Lime 3348
 Kinderhook Sh 3604
 Simpson Dolomite

3670-78TD

Core 3672-74 rec.1
 Dolomite some spotted Sat.
 Core 3674-78 rec.3
 Dolomite some spotted Sat.
 Perf. 7 shots 3667-
 3673 1000' wtr.
 15 mins. rainbow
 of oil

FILE
 BOOK 8 28. 1W
 143 14