

9-2

To: 1 040778
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-23,653
200' W of
NE NE NE, SEC. 18, T. 31 S, R. 13 W/2
4950 feet from S section line
530 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414
Operator: Trisum Ventures, Inc.
Name: 922 Union Ctr. Bldg.
Address: Wichita, KS 67202

Lease Name Pratt Well # 1
County Barber
Well Total Depth 4647 151.02 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 9 a.m. Day: 2 Month: 9 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4607' w/225 sx cement, PBTD 4515', Open hole 4607-47', Perfs at 4603-04, 4536-40, 4460-68, 4431-33, 4398-4400'

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:45 a.m. Day: 2 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 125 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing. SEP 08 1993

INVOICED
I (check) did not observe this plugging.

DATE SEP 14 1993

WV. NO. 38620

Signed [Signature] (TECHNICIAN)
RECEIVED STATE CORPORATION COMMISSION SEP 08 1993 CONSERVATION DIVISION Wichita, Kansas