

To: 1 040779  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-2 API NUMBER 15-007-20,638-A-00-01  
App. SE NW NE, SEC. 18, T. 31 S, R. 13 W/E  
4180 feet from S section line  
1670 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414  
Operator: Trisum Ventures, Inc.  
Name:  
Address 922 Union Ctr. Bldg.  
Wichita, KS 67202

Lease Name Pratt Well # 2  
County Barber 148.36  
Well Total Depth 4565 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 11:30 a.m. Day: 2 Month: 9 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4564' w/150 sx cement, Perfs at 4564-65, 4497-99'  
1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 2 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 5 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 450 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 08 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing. CONSERVATION DIVISION  
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE: SEP 14 1993

INV. NO. 38619

Signed Stephen G. Pfeiffer  
(TECHNICIAN)