

1 060226

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,479-6000

NW NW SE, SEC. 18, T 31 S, R 13 W/EK

695 feet from ~~XX~~/S section line

825 feet from ~~W~~/XX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Dewitt Well # 1

Operator: W. L. Kirkman, Inc.

County Barber

Name & Address P. O. Box 18611

Well Total Depth 4406 143.20 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 27 Month: April Year: 19 84

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2 set at 4406' PBD 4200' Perfs 3746

1st plug pushed a wooden plug ahead of sand and sanded back to 3770' and dumped 5 sx cement on top of sand

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and pumped an additional 150 sx cement.

Bud Metz observed part of the plugging operation
Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3:30 pm Day: 27 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4406' PBD 4200' Perfs 3746'

1st plug pushed a wooden plug ahead of sand and sanded back to 3770' and dumped 5 sx cement on top of sand, 2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,

1 sack huls and 150 sx cement.

Bud Metz observed part of the plugging operation

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun. They recovered 3280' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-7-84

INV. NO. 1388

4-27

RECEIVED

MAY 03 1984

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthie (TECHNICIAN)