

8-8

1 040309

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,667-0600
150' S of
C SE SW, SEC. 19, T. 31 S, R. 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

510 feet from S section line
3300 feet from E section line

Operator: TXO Production Corporation
Name & Address: 1660 Lincoln Street, Suite 1800
Denver, CO 80264

Lease Name Mills Feed Well # 1
County Barber

Well Total Depth 3825 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:45 a.m. Day: 8 Month: 8 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3824' PBD 3812' Perfs at 3736-3740'

1st plug sand back to 3690' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 8 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 650 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

8-15-89 AUG 15 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2100' of 4 1/2" casing
(if additional description is necessary, use BACK of this form) Wichita, Kansas

INVOICED

DATE 8-18-89

INV. NO. 25681

Signed Stephen J. Pfeifer
(TECHNICIAN)