

To: 1 070121
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,108-6000
300' West W/2
NW NW 23, SEC. 23, T 31 S, R 13 W/E
4620 feet from S section line
5250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205
Operator: Mid-Continent Energy Corp.
Name & Address 120 South Market, Suite 310
Wichita, KS 67202

Lease Name Packard Well # 5
County Barber 157.61
Well Total Depth 4665 Arbuckle 25' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co., License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 9 Month: January Year: 19 86

Plugging proposal received from Tom Kern

(company name) Allen (phone) 316-793-5681
Elevation 1589

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite none

1st plug in the Arbuckle with 50 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:15 am Day: 9 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1122' with 50 sx cement, 2nd plug at 250' with 40 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
Signed Dan Goodrow
(TECHNICIAN)

DATE JAN 14 1986

INV. NO. 12041

JAN 13 1986

1-13-1986

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

COLLECTION

1-2-86

Starting Date 12 10 85 month day year

API Number 1 007-22, 108-0600

OPERATOR: License # 5205
Name Mid-Continent Energy Corporation
Address 120 S. Market, Suite 110
City/State/Zip Wichita, KS 67202
Contact Person Bradley R. Buehler
Phone (316) 265-9501

NW, SE, NE, SW Sec 22, Twp 21 S, Rg 13
3630 Ft. from South Line of Section
990 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5418
Name Allen Drilling Company
City/State Great Bend, KS 67530

Nearest lease or unit boundary line 330 feet
County Barber
Lease Name Packard Well # 5
Ground surface elevation 1589 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 X 2 0
Depth to bottom of fresh water 60
Depth to bottom of usable water 200
Surface pipe planned to be set 200
Projected Total Depth 4650 feet
Formation Arbuckle

Well Drilled For: Well Class: Type Equipment:
X Oil SWD X Infield X Mud Rotary
X Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.
cementing will be done immediately upon setting production casing.
Date 12/23/85 Signature of Operator or Agent Title Petroleum Geologist

For KCC Use:
Conductor Pipe Required: feet; Minimum Surface Pipe Required: feet per Alt. 1 2
This Authorization Expires 6-4-86 Approved By 12-4-85

PUSHER
TD FORMATION
SURFACE PIPE @ ELEVATION
ANHYDRITE
STARTING TIME & DATE
COMPLETION TIME & DATE
1st PLUG @ FT. W/ SX
2nd PLUG @ FT. W/ SX
3rd PLUG @ FT. W/ SX
4th PLUG @ FT. W/ SX
5th PLUG @ FT. W/ SX
WATER WELL PLUGGED W/
CEMENT COMPANY
TECHNICIAN

JAN 13 1986
CONSERVATION DIVISION