

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21500-00-00
Spot: NENWSW Sec/Twnshp/Rge: 12-11S-22W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: EMMERTON Well #: 1
County: TREGO Total Vertical Depth: 3870 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3868		150 sx
SURF	8.625	288		200 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2012 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Well had been squeezed @1598' w/400 sx cement
Plugging Hit bridge @800'. Broke through with bailer.
Method: Ordered 320 sx 60/40 4% gel cement. 16 sx gel. 500# hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 12/12/2012 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 3700'. Pumped 16 sx gel followed by 50 sx cement w/200# hulls. Pulled tubing to 1675' and pumped 210 sx cement w/300# hulls. Cement circulated. POOH. Topped off w/35 sx cement. Tied onto backside and pumped 25 sx cement. SIP 450 psi.

Remarks: QUALITY WELL SERVICE TICKET #1445 EMMERTON FEE FUND PROJECT CONTROL #20130052-001

Plugged through: TBG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

MAY 11 2015

RECEIVED

APR 29 2015