

SP  
D

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 9 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-007-00325-0001

Operator's Full Name Kathol Petroleum Inc.

Complete Address 900 Sutton Place Wichita, Ks

Lease Name Olson Well No. 1

Location SE/SE/SE Sec. 5 Twp. 31 Rge. 12 (E) (W) #

County Barber Total Depth 3940

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kathol Petroleum Inc.

Address 900 Sutton Place Wichita, Ks License No. 661

Operation Completed: Hour 1:00 PM Day 7 Month 6 Year 1971

The above well was plugged as follows:

195 ft 10 3/4 surface pipe cemented, circulated. 3940 ft 5 1/2 long  
string cemented with 175 sacks. Top perf. 3700 ft. Set plug at 3650  
ft. Sand back to 3500 ft, 5 sacks cement with bailer. Pulled 3200 ft  
5 1/2. Set 10 ft rock bridge at 180 ft. Fill hole with 4 yds redimix  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 6-9-71

INV. NO. 3823-W