

R

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-007-3044-0000

DEC -1 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Tom-Kat, Inc.

Complete Address: 1127 Wichita Plaza, Wichita, Kansas

Lease Name Olson Well No. # 1

Location @ NW NE Sec. 5 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 3825'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Tom-Kat Drilling, Inc.

Address: 1127 Wichita Plaza, Wichita, Kansas License No.     

Operation Completed: Hour 3:00 PM Day 26th Month Nov. Year 1965

The Above well was plugged as follows:

217' of 8 5/8" surface pipe, cement circulated with 150 sacks. Hole  
was filled with drilling mud to 210', 1st cementing plug, bridged  
solid with dry cement and hulls on fluid at 210', and cemented with  
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged solid with dry cement and hulls on fluid at 40', and  
cemented with 10 sacks to the base of the cellar. Rat hole bridged  
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12-1-65

INV. NO. 2315-W