

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-007-19113-0000

Well Plugging Authority
issued February 28, 1967.

Operator's Full Name Union Texas Petroleum Corporation

3-13-1967

Complete Address: 1200 Skirvin Tower, Oklahoma City, Oklahoma

Lease Name Winter Well No. # 1

Location C NE SW Sec. 7 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 3792'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 11:30AM Day 11th Month March Year 1967

The Above well was plugged as follows:

202' of 8 5/8" surface pipe, cement circulated. 3791' of 4 1/2" long string,
cemented with 75 sacks. Top perferation 3632'. Bottom of the hole was
sanded to 3600', and cemented with 3 sacks, through the dump bailer.
2571' of 4 1/2" long string was recovered from the hole. Fluid in the hole
was bailed down to 200', bridge plug and rock bridge from 200' to 190',
and cemented with 25 sacks at 190'. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/13/67
INV. NO. 4898-W