

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

12-10-1964

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1964

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-007-60675-0000

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name B. E. Shelton

Complete Address: 102 Insurance Bldg., Wichita, Kansas

Lease Name Elliott Well No. # 1

Location C NW NW Sec. 9 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 3820

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sierra Petroleum Company, Inc.

Address: 1015 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 5:00AM Day 9th Month Dec. Year 1964

The Above well was plugged as follows:

208' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 210', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 210', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/10/64
INV. NO. 320-11