

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-007-00073-0000

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

4-13-1964  
RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name George Kisling Well No. # 1

Location SW SW NE Sec. 25 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 4308

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:00PM Day 11th Month April Year 1964

The Above well was plugged as follows:

125' of 8 5/8" surface pipe, cemented with 100 sacks. 4308' of 5 1/2" long  
string, cemented with 100 sacks. Plug back to 3390'. Top perferation  
3375'. Bottom of hole was sanded to 3360', and cemented with 5 sacks.  
Hole was squeezed. 15 sacks of Gel-Mud was pumped into 8 5/8" swage,  
with wiping plug between the mud and cement. 80 sacks of cement was  
pumped into 8 5/8" swage, to pressure of 250 lbs.  
2003' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/15/64

INV. NO. 8933-u