

DISTRICT CONSERVATION AGENT'S REPORT

R

15-007-10069-0000

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 57-25-
LOCATION SW-NE-NE.
SEC. 18 TWP. 31 RGE. 13W

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 3 Lease Grant "C"
Operator H.C.R.G. Address 305-Rule Bldg
Wichita Kan
Field County Bartles
Total Depth 4685- Feet.
Plugging Contractor West Supply Co Inc
Plugging Contractor's License No. 14
Address Chase Kansas

(Describe briefly the manner in which the well was plugged)

8 3/4" 306' Percolated with cement
5 1/2" 4584' Plugged with Baker Plug 4550'
Perforated 4519'-24' hole filled with sand
to 4570' run 5' of cement with dumb pipes
Mud to 300' set rock bridge run 20' of
Cement Mud to 35' set Rock Bridge
run 10' of Cement Pak.

RECEIVED
STATE CORPORATION COMMISSION

M. R. Rivers
District Conservation Agent

Date 8-28-54

CONSERVATION DIVISION
Wichita, Kansas

9-1-1954

PLUGGING
FILE SEC 18 T 31 R 13W
BOOK PAGE 51 LINE 25