

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20948-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 11-17S-34W
1998 feet from S Section Line, 2285 feet from W Section Line
Lease Name: SANDS Well #: 1-11
County: SCOTT Total Vertical Depth: 4900 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 1616 S VOSS RD STE 600
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4425		WITH 2 SX CMT
DVT	4.5	2432		WITH 450 SX CMT
PROD	4.5	4898	0	WITH 175 SX CMT
SURF	8.625	266		WITH 205 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2015 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JASON Company: LANDMARK RESOURCES Phone: (316) 755-3523

Proposed Plugging Method: SET CIBP @ 4425' WITH 2 SX CMT. RUN TBG TO 2480' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2015 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4425' WITH 2 SX CMT. RUN TBG TO 2507' & CIRCULATE CMT TO SURFACE WITH 150 SX CMT. TOOH & TOP OFF 4 1/2" CASING WITH 25 SX CMT. PUMP 25 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
4472	4641		

Received
KANSAS CORPORATION COMMISSION
MAY 04 2015
CONSERVATION DIVISION
WICHITA, KS


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

5/6/15 CKM

District: 01

Signed



(TECHNICIAN)

51A

RECEIVED
APR 27 2015

KCC DODGE CITY