

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23603-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 35-15S-15W
2040 feet from N Section Line, 2300 feet from W Section Line
Lease Name: VERNON Well #: 1
County: RUSSELL Total Vertical Depth: 3448 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3442	2602	130 SX
SURF	8.625	454		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2015 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATION, INC. Phone: (785) 483-1676

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2015 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/07/2015- Sand back to 3150' and bailed 5 sx cement on top.
04/08/2015- Cut 5 1/2" casing at 2602'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 975' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450' and pumped 100 sx cement. Pulled casing to 45' and pumped 40 sx cement w/100 # hulls. Filled cellar.
04/09/2015- Checked on cellar and it was full.
GPS: 38.70571 -098.95960

Perfs:

Top	Bot	Thru	Comments
3330	3334		
3239	3243		
3202	3206		

Remarks: QUALITY CEMENTING TICKET # 933

Plugged through: CSG

5/6/15 CCM

District: 04

Signed Ray A Dinkel (TECHNICIAN) CM

APR 14 2015

KCC WICHITA

APR 24 2015

RECEIVED