

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N, Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25026-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 10-16S-14W  
2310 feet from N Section Line, 1010 feet from W Section Line  
Lease Name: DUANE POPP Well #: 1  
County: BARTON Total Vertical Depth: 3411 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3396	2125	135 SX
SURF	8.625	410		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2015 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/10/2015 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 2125'. Pulled casing to 1475' and pumped 125 sx cement w/300 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 650' and pumped 50 sx cement w/100 # hulls. Pulled casing to 350'. Circulated cement to surface with 90 sx cement. Pulled casing and hole stayed full.  
GPS: 38.67481 -098.86398

Perfs:

Top	Bot	Thru	Comments
3324	3328		
3305	3309		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie 5/6/15 CKM  
(TECHNICIAN) CM

APR 14 2015

KCC WICHITA

Form CP-2/3

APR 24 2015

RECEIVED