

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24440-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 20-34S-3E
2970 feet from S Section Line, 330 feet from W Section Line
Lease Name: MCCORGARY Well #: AVA #1
County: COWLEY Total Vertical Depth: 3834 feet

Operator License No.: 3630
Op Name: MCCORGARY, MARTIN DBA MCCORG
Address: 1180 322ND RD
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2740		
CIBP	4.5	3390		
PROD	4.5	3825	2376	250 SX
SURF	8.625	307		165 SX
T1	2.375	3286		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/29/2015 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MARTIN MCCORGARY Company: MCCORGARY OPERATIONS Phone: (620) 442-4437

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 02/04/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2640', DUMP BAILED 2 SXS CEMENT ON TOP. 2-3-2015, CUT CASING @ 2376', LAYED DOWN 4.5" CASING. 2-4-2015, RIH W/TBG @ 357', XL CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 140 SXS CLASS A COMMON 1% CC TO SURFACE. CEMENT CIRCULATED. XL CEMENT TICKET #1579.

Perfs:

Top	Bot	Thru	Comments
3784	3788	CSG	
3771	3773	CSG	
3282	3288	CSG	
3110	3120	CSG	
3020	3030	CSG	
2673	2674	CSG	

Remarks:

Plugged through: TBG

District: 02

KCC WICHITA Signed

APR 27 2015

RECEIVED

[Signature]
(TECHNICIAN)

5/6/15