

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-22665-00-00
Spot: N2NE Sec/Twnshp/Rge: 31-13S-14W
4620 feet from S Section Line, 1320 feet from E Section Line
Lease Name: BROWN B Well #: 3
County: RUSSELL Total Vertical Depth: 3402 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3398		150 SX
SURF	8.625	935		415 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2015 9:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: GLM CO Phone: (785) 639-1307

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2015 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations: 925' and 350'. Ran tubing to 3250' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1750' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 650' and pumped 75 sx cement w/no returns. Shut down and pulled tubing out of well. WOC. Ran tubing back in to 800' and pumped 100 sx cement w/200 # hulls. Had good flag of cement. Cement circulated out of the braden head and backside. POOH. Topped off casing w/5 sx cement and shut in.

04/21/2015- Checked on fill up. Cement was down 5-6'.

GPS: 38.8387 -098.91463

Perfs:

Top	Bot	Thru	Comments
3332	3334		
3311	3319		
3234	3236		
3082	3086		

Remarks: GLOBEL CEMENTING TICKET # 1642

Plugged through: TBG

5/6/15 OKM

District: 04

Signed Ray A Dinkel

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 01 2015

CONSERVATION DIVISION
WICHITA, KS

APR 23 2015