

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-20963-00-00  
Spot: E2NWNWNE Sec/Twnshp/Rge: 14-17S-34W  
330 feet from N Section Line, 2210 feet from E Section Line  
Lease Name: SCHNEIDER Well #: 1  
County: SCOTT Total Vertical Depth: 4852 feet

Operator License No.: 3581  
Op Name: RED OAK ENERGY, INC.  
Address: 7701 E KELLOGG DR STE 710  
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4650		WITH 2 SX CMT
DVT		2430		WITH 270 SX CMT
PROD	5.5	4851	0	WITH 175 SX CMT
SURF	8.625	223		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2015 2:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: DAVE PAULY Company: RED OAK ENERGY Phone: (316) 250-2045

Proposed Plugging Method: SET CIBP @ 4650'. PLUG AT 2480' TO SURFACE WITH CMT. USE 50 SX CMT TO CHECK BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 04/22/2015 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 4650' WITH 2 SX CMT. RUN TBG TO 2490' & CIRCULATE CMT TO SURFACE WITH 235 SX CMT. TOOH WITH TBG & TOP OFF 5 1/2" CASING WITH 50 SX CMT. CMT FELL BACK TO 120'. 4/24/15: TOPPED OFF 5 1/2" CASING. CMT TO SURFACE. PUMP 15 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
4810	4818		
4742	4746		
4706	4713		

KCC WICHITA  
APR 30 2015

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

5/6/15 CKM

District: 01

Signed E. McLaren  
JA (TECHNICIAN)

RECEIVED  
APR 27 2015  
KCC DODGE CITY