

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-20822-00-00
Spot: NENW Sec/Twnshp/Rge: 17-35S-36W
4365 feet from S Section Line, 3175 feet from E Section Line
Lease Name: ROSE Well #: 3-17
County: STEVENS Total Vertical Depth: 7000 feet

Operator License No.: 6677
Op Name: SANDLIN OIL CORPORATION
Address: 621 17TH ST STE 2055
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6430		WITH 2 SX CMT
PROD	5.5	6991	0	WITH 1580 SX CMT
SURF	9.625	1786		WITH 650 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2015 9:00 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: STEVE HELM Company: MIDWESTERN WELL SERVICE, IN Phone: (620) 624-8203

Proposed Plugging Method: SET CIBP @ 6430' WITH 2 SX CMT. PERFORATE AT 1810' WITH 50 SX CMT, 150# HULLS IN THE LAST 25 SX CMT. PERFORATE AT 650' WITH CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2015 12:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 6430' WITH 2 SX CMT. 1ST PLUG PERFORATE AT 1760' WITH 50 SX CMT, 150# HULLS IN THE LAST 25 SX CMT. 2ND PLUG PERFORATE AT 650'. TBG AT 620' WITH 150 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6624	6636		
6494	6504		
5521	5525		

KCC WICHITA

APR 30 2015

RECEIVED

5/6/15 OCM

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

[Signature]

(TECHNICIAN)

[Signature]

RECEIVED
APR 27 2015
KCC DODGE CITY