

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-033-21612-01-00  
 Spot: N2N2NWNW Sec/Twnshp/Rge: 2-31S-20W  
5076 feet from S Section Line, 4568 feet from E Section Line  
 Lease Name: AMELIA GRACE Well #: 1-2H  
 County: COMANCHE Total Vertical Depth: 5236 feet

Operator License No.: 34192  
 Op Name: SANDRIDGE EXPLORATION AND PRO  
 Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5200		WITH 20 SX CMT
COND	20	120		WITH 345 SX CMT
	II 7	5612	1103	WITH 220 SX CMT
PROD	4.5	9560		WITH 470 SX CMT
SURF	9.625	1050		WITH 750 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/24/2015 9:00 AM  
 Plug Co. License No.: 34602 Plug Co. Name: KEY ENERGY SERVICES, LLC  
 Proposal Rcvd. from: VINCE Company: KEY ENERGY SERVICES, LLC Phone: (713) 757-5441

Proposed Plugging Method: CIBP @ 5200' WITH 20 SX CMT. PLUG AT 1100' WITH 100 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 04/24/2015 1:30 PM KCC Agent: ERIC MACLAREN

**Actual Plugging Report:**

SET CIBP @ 5200' WITH 20 SX CMT. 1ST PLUG AT 1089' WITH 100 SX CMT. 2ND PLUG AT 384' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

**Perfs:**

Top	Bot	Thru	Comments
8408	8709		
8037	8336		
7639	7946		
7294	7578		
6923	7244		
6539	6851		
6180	6500		
5825	6033		
5437	5736		

KCC WICHITA  
 APR 30 2015  
 RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL 3% CC BY KEY ENERGY SERVICES. TMD= 9560'

Plugged through: TBG

5/6/15 ckm

District: 01

RECEIVED  
 APR 27 2015  
 KCC DODGE CITY

Signed [Signature]  
 (TECHNICIAN)