

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-21803-00-00  
Spot: SESESW Sec/Twnshp/Rge: 3-22S-16W  
330 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: BUSTER Well #: 2-3  
County: PAWNEE Total Vertical Depth: 4110 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 621 17TH ST STE 1155  
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1025		WITH 450 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2015 3:15 AM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: ALAN LOFTIS Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 4015' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 04/20/2015 5:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 4015' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.


Plugged through: DP

5/6/15 CKM

District: 01

Signed   
(TECHNICIAN)

RECEIVED  
APR 21 2015  
KCC DODGE CITY 

KCC WICHITA   
APR 27 2015  
RECEIVED