

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-003-19334-00-01
Spot: NWSWNESE Sec/Twnshp/Rge: 6-23S-19E
1916 feet from S Section Line, 1032 feet from E Section Line
Lease Name: COLONY GAS STORAGE Well #: 28
County: ANDERSON Total Vertical Depth: 985 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	878		250 SX
SURF	10	11		0 SX

Well Type: GWI UIC Docket No: _____ Date/Time to Plug: 11/24/2014 12:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Revd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: KILL WELL. PULL 4.5" TUBING AND PACKER FROM WELL. SET CEMENT RETAINER RIGHT ABOVE WHERE PACKER WAS. STAB RETAINER WITH WORKSTRING AND PUMP CEMENT BELOW INTO FORMATION. PULL OUT OF RETAINER AND PUMP CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP WELL OFF WITH CEMENT. CUT WELL OFF 3' BELOW SURFACE.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 11/26/2014 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

REMOVE 4.5-INCH AND PACKER FROM WELL. SET CEMENT RETAINER AT 840 FEET, THEN WASH KILLING MUD OUT. RAN IN WORKSTRING AND STABBED RETAINER. PUMP CEMENT BELOW RETAINER TO A PRESSURE OF 1200 PSI. PULL WORKSTRING ABOVE RETAINER AND PUMP CEMENT TO SURFACE. A TOTAL OF 163 SACKS OF CLASS A PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
878	985		

RECEIVED
KCC DIST # 3
APR 29 2015
CHANUTE, KS

Received
KANSAS CORPORATION COMMISSION
MAY 04 2015
CONSERVATION DIVISION
WICHITA, KS

LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]

(TECHNICIAN)

5/6/15 CKM