

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-003-19353-00-01  
Spot: NENENENW Sec/Twnshp/Rge: 7-23S-19E  
5133 feet from S Section Line, 2724 feet from E Section Line  
Lease Name: COLONY GAS STORAGE Well #: 47  
County: ANDERSON Total Vertical Depth: 999 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	905		220 SX
SURF	10.75	20		0 SX

Well Type: GW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2014 12:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Revd. from: STERLING BARKER Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: KILL WELL. PULL 4.5" TUBING AND PACKER FROM WELL. SET CEMENT RETAINER RIGHT ABOVE WHERE PACKER WAS. STAB RETAINER WITH WORKSTRING AND PUMP CEMENT BELOW INTO FORMATION. PULL OUT OF RETAINER AND PUMP CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP WELL OFF WITH CEMENT. CUT WELL OFF 3' BELOW SURFACE.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE  
Date/Time Plugging Completed: 11/05/2014 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

REMOVE 4.5-INCH AND PACKER FROM WELL. SET CEMENT RETAINER AT 860 FEET, THEN WASH KILLING MUD OUT. RAN IN WORKSTRING AND STABBED RETAINER. PUMP CEMENT BELOW RETAINER TO A PRESSURE OF 1200 PSI. PULL WORKSTRING ABOVE RETAINER AND PUMP CEMENT TO SURFACE. A TOTAL OF 233 SACKS OF CLASS A PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
905	999		

RECEIVED  
KCC DIST # 3  
APR 29 2015  
CHANUTE, KS  
LS


Received  
KANSAS CORPORATION COMMISSION  
MAY 04 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

E. L. Johnson