

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26775-00-00
Spot: SENENWSW Sec/Twnshp/Rge: 5-12S-17W
2300 feet from S Section Line, 1190 feet from W Section Line
Lease Name: STAAB SHUTTS Well #: 1
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 6037
Op Name: STAAB OIL CO., A GENERAL PARTNER
Address: 1607 HOPEWELL RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/15/2015 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC.
Proposal Rcvd. from: GEORGE Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 735-4503

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 04/15/2015 9:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st plug @3571 w/50 sx
2nd plug @1375 w/50 sx
3rd plug @790 w/100 sx
4th plug @260 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: GLOBAL

Plugged through: DP

District: 04

Signed

Richard Williams
(TECHNICIAN)

CM

5/6/15 cpm

APR 15 2015

KCC WICHITA

APR 24 2015

RECEIVED