

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19193-00-00
Spot: SWNWSWSE Sec/Twnshp/Rge: 10-34S-11E
868 feet from S Section Line, 2388 feet from E Section Line
Lease Name: JIENCKE Well #: 4
County: CHAUTAUQUA Total Vertical Depth: 1150 feet

Operator License No.: 34680
Op Name: TDOT OIL, INC.
Address: PO BOX 117
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	1150		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2015 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: TIM DOTY Company: _____ Phone: (620) 331-9791

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 750' and 350'. Run 1" back in and spot 50' plug of cement at 750'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 03/11/2015 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1120' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 650' and 350'. Ran 1" back into 650' and spotted 15 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 152 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
APR 21 2015
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED BECAUSE IT WAS ABANDONED AND COULD NOT BE TA'D.

Plugged through: TBG

5/16/15 CPM

District: 03

Signed Duane A Sims
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

APR 27 2015

RECEIVED