

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25825-00-00
Spot: N2SESESE Sec/Twnshp/Rge: 28-18S-24W
487 feet from S Section Line, 334 feet from E Section Line
Lease Name: CRANSTON Well #: 1
County: NESS Total Vertical Depth: 4440 feet

Operator License No.: 34876
Op Name: TRIPLE CROWN OPERATING LLC
Address: 2201 S. UTICA PL STE 100
TULSA, OK 74114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4180		
CIBP		4305		
CIBP		4335		
PC	5.5	1585		WITH 260 SX CMT
PROD	5.5	4396	0	WITH 116 SX CMT
SURF	8.625	254		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2015 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BRIAN GABEL Company: BARRACUDA OPERATING Phone: (785) 731-5074

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS, SPACER TO 1600' THEN CMT TO SURFACE. 50 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2015 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 50 SX CMT & 150# HULLS, THEN 47 BBL SPACER, THEN 165 SX CMT. MAXIMUM PRESSURE 1700#. SHUT IN WITH 1200#. TIED ONTO BACKSIDE & PUMPED 10 SX CMT DOWN THE BACKSIDE. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4436	4490		
4362	4374		
4262	4268		
4115	4126		

KCC WICHITA

APR 27 2015

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

RECEIVED

Plugged through: CSG

5/6/15 CRM

District: 01

RECEIVED
APR 21 2015
KCC DODGE CITY

Signed

Michael Maier

(TECHNICIAN)

JR