

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-00192-00-01
Spot: NENWSE Sec/Twnshp/Rge: 9-32S-6E
2357 feet from S Section Line, 1632 feet from E Section Line
Lease Name: JACK BOUCHER V Well #: 1-9 OWWO
County: COWLEY Total Vertical Depth: 3429 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3396		125 SX
SURF	8.625	212		190 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2015 8:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 02/11/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3020', DUMP BAILED 2 SXS CEMENT ON TOP OF CIBP. CUT CASING @ 2530', LAYED DOWN 60 JOINTS 5.5 CASING. (2530'). RIH W/ TBG @ 380'. SDON. 2-11-2015, QUALITY WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 195 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. QUALITY CEMENT TICKET #6338.

Perfs:

Top	Bot	Thru	Comments
3148	3162		CSG
3125	3130		CSG
3095	3101		CSG
3073	3077		CSG
3060	3064		CSG

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

5-5-2015
Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 05 2015

CONSERVATION DIVISION
WICHITA, KS

5/6/15 CKM

✓