

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20066-00-00  
Spot: NESESE Sec/Twnshp/Rge: 13-17S-28W  
1001 feet from S Section Line, 306 feet from E Section Line  
Lease Name: DAVIS B Well #: 2  
County: LANE Total Vertical Depth: 4587 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4130		WITH 2 SX CMT
DVT	5.5	2097		WITH 450 SX CMT
PROD	5.5	4557	0	WITH 325 SX CMT
SURF	8.625	357		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/15/2015 3:00 PM  
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC  
Proposal Rcvd. from: JOE RUPP Company: VESS OIL Phone: (316) 682-1537

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 2 SX CMT. RUN TBG TO 2100' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/14/2015 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4130' WITH 2 SX CMT. RUN TBG TO 2100' & PUMPED 230 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 50 SX CMT. COULDN'T TIE ONTO BACKSIDE HEAD WAS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4416	4426		
4190	4206		
4164	4169		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

5/6/15 CKM

District: 01

Signed Michael Maier  
KCC WICHITA (TECHNICIAN)

RECEIVED  
APR 21 2015  
KCC DODGE CITY

APR 27 2015  
RECEIVED  
4-27-2015