

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19216-00-00
Spot: SESESESE Sec/Twnshp/Rge: 18-33S-3E
145 feet from S Section Line, 197 feet from E Section Line
Lease Name: BELL Well #: 1
County: COWLEY Total Vertical Depth: 3254 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3254	397	0 SX
SURF	8	203		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/16/2015 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: WD SHORT OIL CO LLC Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/18/2015 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 3250', ELITE CEMENTING PUMPED 30 SXS CLASS A COMMON & DISPLACED IN CASING. WAITED 2 HOURS TAGGED CEMENT @ 2930'. RIH ON WIRELINE, CUT 5 1/2" CASING @ 397', LAYED DOWN 12 JOINTS 5 1/2" CASING (397'). 2-18-2015, RIH W/ TBG @ 380', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:00 PM, 2-18-2015. ELITE CEMENT TICKET #2062.

Perfs:

Top	Bot	Thru	Comments
3232	3253	CSG	

Remarks:

Plugged through: TBG

5/6/15 OCM

District: 02

Signed Duane Krueger
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 05 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

✓