

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19218-00-00
Spot: SESWNE Sec/Twnshp/Rge: 19-32S-3E
2920 feet from S Section Line, 1722 feet from E Section Line
Lease Name: CARSON Well #: 2B
County: COWLEY Total Vertical Depth: 2599 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	40		
PROD	5.5	2574		50 SX
SURF	10	1875		0 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/10/2015 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: WD SHORT OIL CO., LLC Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2550 W/ 5 SXS PERF & CIRC 375'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/19/2015 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2599', ELITE CEMENTING PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING. WAITED 2 HOURS TAGGED CEMENT @ 2199'. 2-11-2015, RIH ON WIRELINE, CUT 5 1/2" CASING @ 576', LAYED DOWN 18 JOINTS 5 1/2" CASING (576'). RIH ON WIRELINE, CUT 8.25" & 10" CASINGS @ 474'. LAYED DOWN 8.25 & 10" CASINGS (474'). 2-12-2015, RIH W/TBG @ 378', ELITE CEMENTING SERVICES MIXED & PUMPED 250 SXS 60/40 POZMIX 4% GEL. 2-13-2015, RIH W/TBG @ 378', ELITE CEMENTING MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 3% CC. PULLED TUBING @ 283', ELITE CEMENTING MIXED & PUMPED 540 SXS 60/40 POZMIX 4% GEL 3% CC. WAITED 6 HOURS, TAGGED CEMENT PLUG @ 125'. 2-19-2015, RE-TAGGED TOP CEMENT PLUG @ 152'. RIH W/TBG @ 142', ELITE CEMENTING MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL 3% CC & DISPLACED IN CSG. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 40'. RIH W/TBG @ 40', ELITE CEMENTING MIED 7 PUMPED 125 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 12:00 PM, 2-19-2015. ELITE CEMENT TICKET #2139 & 2064.

Perfs:

Top	Bot	Thru	Comments
2574	2599	OH	

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 05 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

5-5-2015

5/6/15 acm