

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24253-00-00
Spot: SESENE Sec/Twnshp/Rge: 19-32S-3E
2981 feet from S Section Line, 322 feet from E Section Line
Lease Name: CARSON Well #: 4B
County: COWLEY Total Vertical Depth: 3528 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3450		
PROD	5.5	3528	576	255 SX
SURF	8.625	322		391 SX
T1	2.875	3486		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2015 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: WD SHORT OIL CO Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 2570 W/5 SXS PERF & CIRC 375'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/10/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2570'. DUMP BAILED 5 SXS CEMENT ON TOP. SDON. 2-10-2015, RIH W/ TBG @ 384', ELITE CEMENTING SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 65 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM, 2-10-2015. ELITE CEMENT TICKET #2138.

Perfs:

Top	Bot	Thru	Comments
2622	2632		CSG

Remarks: DUG OUT CELLER/ CEMENT ON BACKSIDE

Plugged through: TBG

5/6/15 CPM

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 05 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

5-5-2015

SK