


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

15-173.61686-0000
WELL PLUGGING RECORD

Form CP-4

Sedgwick County. Sec. 36 Twp 28S Rge. (E) 1 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner Kewanee Oil Company

Lease Name Gladys Unit - Tract 10 Well No. 11 WI

Office Address P. O. Box 157, Haysville, Kansas 67060

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 10-19- 19 55

Application for plugging filed 8-11- 19 71

Application for plugging approved 8-16- 19 71

Plugging commenced 8-23- 19 71

Plugging completed 10-6- 19 71

Reason for abandonment of well or producing formation no longer need as
input well.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey

Producing formation Mississippi Depth to top 3199 Bottom Total Depth of Well 3219 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City		2669		8-5/8"	152'	none
				5-1/2"	3196'	2326'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Ran Halliburton EZ drill packer on
2" tubing set @ 3113'. Pumped 100
sacks Pozmix @ 2100#. Pulled out
and dumped 1/2 barrel cement on top
of packer.

Ripped casing and recovered 2326'. Set
rock bridge from 220-235'. Dumped
4 cu.yds. ready mix to surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering Company 10-22-1971

Address Eldorado, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
S. A. Park (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Park

P. O. Box 157, Haysville, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 71

My commission expires 8-10-75 Billie Oden Notary Public.



Gladys Unit

Tr. 10 # 11

P

E. H. Adair Oil Company
Wichita 7, Kansas.

E. H. Adair Oil Company, et al
L. Wright No. 11
NE SE, NE. of
Sec. 36-28S-1W.
Sedgwick County, Kansas.
Elevation: 1284

Contractor: Adair Rig No. 3
Comm.: 10-12-55
Comp.: 10-19-55
8-5/8 @ 152 ft. w/100 sx.
5-1/2 @ 3196 ft. w/100 sx.

15-173-01686-0000

Figures indicate bottoms of Formations

8-5/8	@	152	Shale	to	2928
Lime	to	500	Lime		2954
Lime & shale		1660	Black shale		2957
Lime		1695	Limey shale		3018
Lime & shale		1915	Black shale		3020
Lime		2140	Shale		3052
Shale & lime		2320	Black shale		3053
Sand		2458	Limey shale		3076
Shale & lime		2470	Black shale		3078
Shale		2669	Shale		3095
Lime		2757	Lime		3110
Oolitic lime		2764	Black shale		3112
Lime		2777	Limey colored shale		3150
Black shale		2782	Black shale		3152
Oolitic lime		2787	Limey colored shale		3176
Lime		2863	Chert		3178
Shale		2903	Lime		3199
Lime		2910	Dolomite		3200
			R.T.D.		3200

Tops

Kansas City	2669	(-1385)
Miss. Lime	3178	(-1894)
Miss. Dolomite	3199	(-1915)

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1971
CONSERVATION DIVISION
Wichita, Kansas

Certified correct:

Sherrill Compton - Geologist.