


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

15-173.01687-0000
WELL PLUGGING RECORD

Form CP-4

NORTH



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 36 Twp. 28S Rge. (E) 1 (W)
Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner Kewanee Oil Company
Lease Name Gladys Unit, Tract 10 Well No. 12
Office Address P. O. Box 157, Haysville, Kansas 67060
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 10-28-1955
Application for plugging filed 8-11-1971
Application for plugging approved 8-16-1971
Plugging commenced 8-23-1971
Plugging completed 10-8-1971
Reason for abandonment of well or producing formation High WOR.

If a producing well is abandoned, date of last production 1-26-1964
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey
Producing formation Mississippi Depth to top 3204 Bottom _____ Total Depth of Well 3207 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City		2671'		8-5/8"	156'	none
				5-1/2"	3199'	2016'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran Halliburton EZ drill packer on 2" tubing set @ 3113'. Pumped 100 sacks Pozmix @ 1700#. Pulled out and dumped 1/2 barrel cement on top of packer.

Ripped casing and recovered 2016' of 5-1/2" casing. Set rock bridge from 220-235'. Dumped 4 cu.yd. ready mix to surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering Company
Address Eldorado, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
S. A. Park (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. Box 157, Haysville, Kansas
(Address)

Sworn to before me this 18th day of October, 1971



Billie Oden
Notary Public.

E. H. Adair Oil Company
Wichita 7, Kansas.

15-173-61687-0000

Glady's Unit

Tr. 10 #12

E. H. Adair Oil Company, et al.
L. Wright No. 12
Sec. 36-28-14.
NE SW NE
Sedgwick County, Kansas.

Comm. 10-20-55
Comp. 10-28-55
Contractor: Adair, Rig #3
8-5/8 @ 156 w/145 ex.
5-1/2 @ 3199 w/100 ex.

Elev. 1284 K.B.

Figures indicate bottoms of Formations

Clay & Sand	to	45	Black shale	to	2832
Shale		150	Oolitic lime		2835
Lime		156	Lime		2863
Lime & shale		215	Shale		2900
Lime		595	Limey shale		2932
Shale & lime		1995	Oolitic lime		2938
Shale		2049	Lime		2957
Lime & shale		2081	Black shale		2965
Shale		2316	Lime		2998
Lime		2319	Limey shale		3019
Shale		2351	Black shale		3022
Sand		2386	Shale		3040
Shale		2396	Shale & lime		3057
Sand		2458	Black shale		3060
Shale		2466	Shale		3073
Lime		2483	Lime		3082
Shale		2671	Black shale		3086
Lime		2676	Limey shale		3095
Shale		2678	Shale		3099
Lime		2726	Shaley lime		3117
Shale		2738	Black shale		3120
Lime		2758	Lime & colored shale		3135
Shale		2759	Lime		3140
Lime		2761	Colored shale		3146
Oolitic lime		2764	Lime		3155
Lime		2768	Black shale		3157
Shale		2770	Limey colored shale		3184
Lime		2780	Chert		3189
Black shale		2782	Lime		3204
Oolitic lime		2786	Dolomite		3207
Lime		2830	R.T.D.		3207

Geological Tops

Lansing	2316	-1032
Stalnaker	2351	-1067
K.C.	2671	-1387
Miss. Chert	3184	-1900
Miss. Lime	3189	-1905
Miss. Dolomite	3204	-1920

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1971
CONSERVATION DIVISION
Wichita, Kansas

Certified correct:

K. W. Johnson - Geologist.