

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

RECEIVED

SEP 2 1982
9-2-82
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 26 TWP. 28 RGE. 12W E/W
Location as in quarters or footage from lines:
C NW NW

Locate Well
correctly on above
Section Pratt.

Lease Owner Raymond Oil Company, Inc.
Lease Name Megaffin #1 Well No. _____
Office Address One Main Place Suite 900 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-23-82
Plugging completed 8-27-82
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 2856'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	311'	none
				4-1/2"	2855'	2097'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped bottom with 30 sacks cement, shot casing @2165' and 2098', pulled a total of
63 joints of 4-1/2" casing. Plugged well with 4 sacks hulls, 25 sacks 50/50 pos,
4% gel, 3% cc, 20 sacks gel, 1 sack hulls, 8-5/8" plug, 125 sacks 50/50 pos, 4% gel,
3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained; and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 31st. day of August, 19 82



Irene Hoover
Notary Public.

My Commission expires: _____

WELL LOG

COMPANY Raymond Oil Company

SEC. 26 T. 28S R. 12W

FARM Megaffin No. 1

NO. 1

LOC. C ^{NW} NW

TOTAL DEPTH 2856'


COUNTY Pratt County, Kansas

COMM. 8-14-75

COMP. 8-21-75

CONTRACTOR DaMac Drilling Company

CASING 8 5/8" @ 311' w/300 sx.



ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 235	Sand
235 - 415	Red Bed
415 - 1415	Red Bed and Shale
1415 - 2856	Shale and Lime
2856	RTD

RECEIVED
STATE CORPORATION COMMISSION


AUG 20 1982

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Marlene Mendenhall of DaMac Drilling Company, Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Megaffin No. 1 well.

 DONALD SLOUP
STATE NOTARY PUBLIC
Barton County, Kansas
My Commission Expires
November 11, 1978

Subscribed and sworn to before me this 16th day of September 19 75

My Commission Expires: 11-11-78

Marlene Mendenhall
Donald Sloup
NOTARY PUBLIC

XC: MRS
State