

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.--82-3-117

API NUMBER 15-151-21,962-00-00

LEASE NAME SKILES

WELL NUMBER #1-30

2086 Ft. from S Section Line

4726 Ft. from E Section Line

SEC. 30 TWP. 28 RGE. 12 (E) or (W)

COUNTY Pratt

Date Well Completed 1/31/90

Plugging Commenced 7/24/90

Plugging Completed 7/27/90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS 6427 E. Kellogg, Wichita, KS 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/16/90 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well loc. attached?

Producing Formation None Depth to Top Bottom T.D. 4749

PBTD: 4450

Show depth and thickness of all water, oil and gas formations.

Perfs: 4480-4492, 4496, 4350-4370  
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8"	80'	None
				8 5/8"	1116'	None
				4 1/2"	98 jts	98 joints

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 50' above top perfs plus 4 sacks cement. Found free point at 3600'. Cut off and pulled 98 joints. Halliburton top hole plugged: 300# hulls, 10 sacks gell, 50 sacks cement, 10 gel, 100# hulls, 8 5/8" plugged with 50 sacks cement, 60/40 Poz, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847, Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Company STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Pratt, ss. 1-24-91  
JAN 24 1991

Elywn H. Nagel (Signature of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Elywn H. Nagel

(Address) P.O. Box 780167, Wichita, KS 67278

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 19 91



Notary Public

My Commission Expires

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SKILES #1-30  
Located: C NW SW, Section 30-28S-12W, Pratt County, Kansas

OWNER: F. G. Holl Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 27, 1989  
COMPLETED: December 19, 1989

TOTAL DEPTH: 4749'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 84 Clay and Shale	Set 84' of 13 3/8" conductor. Cemented with Redi-Mix to surface. Job complete at 1:30 PM, 11-27-89.
84 - 215 Sand and Clay	Ran 27 joints 8 5/8" used 24# casing. 1105.38' pipe set at 1116.88' K.B. Cemented with 400 sacks of Howco Light, followed with 175 sacks 40/60 Pozmix, with 2% gel and 3% cc. Plug down at 8:00 PM, 12-7-89, by Howco.
215 - 705 Red Bed-	
705 - 1120 Shale	
1120 - 4749 Lime and Shale	Ran 133 joints used 4 1/2", 10.5# casing. 4730' pipe set at 4738' K.B. Cemented with 100 sacks Howco Light, followed with 125 sacks 50/50 Pozmix with regular F. G. Holl additives. Plug down at 5:30 AM, 12-19-89, by Howco.

Deviation Surveys: 1° at 215'  
3/4° at 310'  
3/4° at 440'  
1/2° at 555'  
3/4° at 801'  
1° at 1120'  
3/4° at 4200'

RECEIVED  
STATE CORPORATION COMMISSION

APR 23 1990

CONSERVATION DIVISION  
Wichita, Kansas