

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Sumner County, Sec. 27 Twp. 34S Rge. 3 (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Herndon Drilling Company

Lease Name J. M. Smock Well No. 1

Office Address Drawer 489, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3/31/57 19

Application for plugging filed 3/31/57 19

Application for plugging approved 3/31/57 19

Plugging commenced 3/31/57 19

Plugging completed 3/31/57 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington, Geuda Springs, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4785 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 40 feet to 640 feet for each plug set.

Hole was filled to 640 feet with rotary mud. Plug was set at 640 feet. 15 Sx. cement was mixed and poured in hole. Hole was filled to 40 feet and plug was set at 40 feet. 10 Sx. cement was mixed and poured in hole. Filled to bottom of cellar and steel cap was welded on casing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Herndon Drilling Company

Address Drawer 489, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss. Tom Elliott

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Drawer 489, Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 57

My commission expires January 27, 1960

Notary Public.

PLUGGING
FILE SEC. 27 T 34 R 3W
BOOK PAGE 3 LINE 24

RECEIVED
STATE CORPORATION COMMISSION
APR 5 - 4-5-1957
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG ON SMOCK #1

Spudding date: 3/8/57
Date casing set: 3/14/57
Date rotary completed: 3/31/57
Date cable completed:

Location:

NW NW NW, Section 27-34S-3W, Sumner County, Kansas

FROM	TO	FORMATION	REMARKS
0	654	Surface Hole	Ran 21 Jts. 24# 8-5/8" Casing, set @ 653' and cemented w/650 Sx. Pozmix & 2% C.C.
654	875	Shale	
875	1218	Shale & Lime	
1218	1425	Shale	
1425	2850	Shale & Lime	
2850	3060	Lime	
3060	3345	Lime & Shale	
3345	3470	Shale & Sand	
3470	4358	Shale & Lime	
4358	4382	Lime	
4382	4453	Lime & Chert	
4453	4716	Lime	
4716	4785	Shale	
4785		Total Depth	

Plugging Record
Hole was filled to 640' w/rotary mud. Plug set @ 640' w/15 Sx. Cement. Hole was filled to 40' and plug set w/10 Sx. Cement. Filled to bottom of cellar and steel cap was welded on casing.

RECEIVED
STATE COMMISSION
APR 5 1957
DIVISION

Subscribed and sworn to before me this 2nd day of April, 19 57.

I certify the above and foregoing to be a true and exact copy of the original driller's log on the Smock #1.

HERNDON DRILLING COMPANY

[Signature]
Notary Public
My commission expires: 1-27-60

By: *[Signature]*
Title: Assistant Secretary

PLUGGING
SEC 27 T 34 R 3W
BOOK PAGE 3 LINE 24