



STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Summer County, Sec. 15 Twp. 34 Rge. 4W (E) (W)
 Location as "NE/CNWxSWx" or footage from lines SW 1/4 SE 1/4
 Lease Owner Continental Oil Company
 Lease Name Dial Well No. 1
 Office Address Box 30 Lyons, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed 19
 Application for plugging filed June 21, 1962 19
 Application for plugging approved June 22, 1962 19
 Plugging commenced June 26, 1962 19
 Plugging completed June 29, 1962 19
 Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie Leon, Ks,
 Producing formation Depth to top Bottom Total Depth of Well 4600 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					XXXXXX	
				10 3/4	225	none
				5 1/2		3889

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in and cleaned out cellar, measured T.D. and sanded to 4350'. Dumped 5 sacks cement and welded on 5 1/2" collar. Started working pipe. Worked pipe and shot well @ 3860'. Pulled 21 fts of pipe. Pulled pipe, and plugged well with mud. Built rock bridge @ 235'. Dumped 15 sacks cement and filled hole and rock bridge. Capped well with 8 sacks cement. Cut off 10 3/4 and welded on cap.

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
 Address Box 221 Great Bend, Kansas

CONSERVATION DIVISION
 WICHITA, KANSAS
 7-10-1962

STATE OF Kansas, COUNTY OF Rice, ss.
 J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

(Address)


SUBSCRIBED AND SWORN to before me this 6th day of July, 1962

My commission expires May 5, 1965

Notary Public.



GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLERS WELL LOG

LJM-175

 15-191-00765-0000

JOHN DIAL #1
 SW 1/4 SE SECTION 15-34S-4E
 SUMNER COUNTY, KANSAS

COMMENCED: MAY 8, 1962
 COMPLETED: JUNE 9, 1962

OPERATOR - CONTINENTAL OIL COMPANY

DEPTH		EXPLANATION	REMARKS
From	To		
0	40	SURFACE LAY & SHELLS	
40	230	RED ROCK & SHALE	RAN 259.59' OF 10-3/4" CASING, SET @ 225' w/ 130 SACKS CEMENT.
230	680	SHALE	
680	995	SHALE & LIME	
995	1182	LIME & SHALE	
1182	1655	LIME	
1655	2815	LIME & SHALE	
2815	3000	SHALE & SHELLS	
3000	3225	LIME & SHALE	
3225	3362	SHALE	
3362	3450	SAND	
3450	3515	LIME & SHALE	
3515	3630	SHALE & SHELLS	
3630	3719	LIME & SHALE	
3719	4242	LIME	
4242	4377	SHALE & LIME	
4377	4430	LIME	
4440	4524	CHERTY LIME	
4524	4568	LIME	
4568	4595	CHERT & LIME	
4595	4639	LIME	
4639	4662	CHERT & LIME	
4662	4708	LIME	
4708	4755	SHALE	
4755	4780	SHALE & LIME	
4780	4788	SHALE	
4788	4905	SAND	
4906	4965	SANDY SHALE	
4965	4987	LIME & SHALE	
4987	5005	LIME	
5005	TD		RAN 174 JOINTS 5-1/2" CASING, SET @ 4510 w/ 300 SACKS CEMENT.



I, JACK W. GABBERT, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN SW 1/4 SE OF SECTION 15-34S-4E, SUMNER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

JACK W. GABBERT
 JACK W. GABBERT

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 14TH DAY OF JUNE, 1962, PERSONALLY APPEARED JACK W. GABBERT TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HERETO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1965

JED
 COMMISSIONER
J. W. McKenzie
 J. W. MCKENZIE, NOTARY PUBLIC

JUL 10 1962

CONSERVATION DIVISION,
 WICHITA, KANSAS