

MUSGROVE PETROLEUM CORPORATION  
518 PETROLEUM BUILDING  
WICHITA 2, KANSAS

See # KS NM  
69306

15-129-10445.00-20

WELL COMPLETION DATA—Recompletion in L.K.C. Date November 28, 1956

NAME ROLL (ISU #59) No. 4 Pool Interstate County Morton

Legal Description C SE NE Sec. 29 Twp. 34S Rge. 43W

660' From the South Line 660' From the East Line of the NE Qtr.

Drilled by Musgrove Petroleum Corporation, Inc. Operated by Musgrove Petroleum Corp., Inc.

Cable Tools by Musgrove Petroleum Corporation, Inc., Rotary Bushing T. D. 4357'

All Measurements Rotary Bushing and Rotary Bushing is 11.98' Feet above the top of the Braden

Head on the Surface Casing R. B. Elevation 3499' Ground Level Elevation 3489'

Surface CSG. Set at 1160' Feet. Make Nat. Grade A Weight .188 Ga.

RGE. 3 Set With 600 Sacks of Cement by Halliburton

Type of Cement Posmix Size of CSG. 8-5/8" O.D.

Oil String Set at 4256' Feet. Make J-55 Grade A Weight 14#

RGE. 3 Set with 225 Sacks of Cement by Halliburton

Type of Cement Common Size of CSG. 5 1/2" O.D.

Type Centralizer Halliburton Shoe Halliburton Float Halliburton

Centers of Centralizer Located at R. B. 4250' 4200' 4150' 4105'

Top of Float at 4226.35' Length of Shoe Joint 29.65' over all No. Plugs 2

Kind of Plugs Rubber & Plastic - top and bottom Feet of Open Hole by Rotary 1'

Date Spudder Moved In 11-25-56 Total Spudder Hours 60

Date Spudder Finished 11-28-56 Total Swab Rubbers used 4

Completion From 4166' To 4170' In The Purdy Sand

Brief Sample Desc., Each Run of Bit, Along W/ Test, Perforations, and Well Reaction:

REMARKS: Perforated from 4166' to 4170' - 4 Shots per foot w/ McCullough Glass Jets.

Plug Back T.D. - 4207' *(Involved in 26 unit KSNM 74120X)*

Kansas Corporation Commission

Acid or Fracture, Maximum Pressure Minimum Pressure Acid Feeding Press.

REMARKS: No acid used.

Tests: Flowing through 1/2" choke

Had gas to surface immediately.

Had oil to surface in 1 hour.

6-hour test - Averaged 20 bbls. oil per hour, no water.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 22 1957

CONSERVATION DIVISION  
Wichita, Kansas

Please fill out completely any additional information. Completion in other zones should be noted in their proper order as above. Fill in the wells and their number on the following Plat:

PERSON COMPLETING THIS WELL:


6	5	4	3	2	1
7	8	9	10	11	12
13	14	15	16	17	18
19	20	21	22	23	24
25	26	27	28	29	30
31	32	33	34	35	36

G. W. Sowles

T 34S  
R 43W  
City Morton