

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 32 Twp. 29S Rge. (K) 9 (W)

Location as "NE/CNW%SW%" or footage from lines NE/4 SE/4 32-29S-9W

Lease Owner Beardmore Drilling Company, et al

Lease Name Adelhardt Well No. 1

Office Address 700 - One Twenty Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-2 19 68

Application for plugging filed 5-2 19 68

Application for plugging approved 5-2 19 68


Plugging commenced 5-2 19 68

Plugging completed 5-2 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sand		0	30			
Red Beds		30	202	8 5/8"	202	- 0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

0 To 40' - 10 Sacks Cement

40' - Wood Plug

40' To 125' - Heavy Mud

125' To 200' - 25 Sacks Cement

200' - Wood Plug

200' to 4,262' - Heavy Mud

Also: 2 Sacks Cement in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

700 - One Twenty Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN before me this 6th day of May, 19 68

Leonard P. Tolle
Notary Public.

My commission expires 1-28-72



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

ADELHARDT #1
C NE SE SECTION 32-29S-9W
KINGMAN COUNTY, KANSAS

COMMENCED: APRIL 19, 1968
COMPLETED: MAY 3, 1968

OPERATOR - BEARDMORE DRILLING Co.

DEPTH	FORMATION	REMARKS
FROM	To	
0	30	SAND
30	202	RED BED
202	350	RED BED
350	675	RED BED AND SHELLS
675	1390	SHALE AND SHELLS
1390	1735	SHALE AND LIME
1735	1905	LIME
1905	3135	LIME AND SHALE
3135	3340	LIME
3340	3560	SAND AND SHALE
3560	4061	LIME
4061	4222	LIME AND SHALE
4222	4262	LIME
4262	TD	DRY AND ABANDONED.

RAN 10 JOINTS 8-5/8" CASING, SET @ 202' w/175 SACKS-CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1968
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE SE SECTION 32-29S-9W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 6TH DAY OF MAY, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires FEBRUARY 1, 1972.

