

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 33 Twp. 29 Rge. 9W (#) (W) X

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Petroleum, Inc.

Lease Name Bohrer 'B' Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 8-22 19 57

Application for plugging filed 6-24 19 64

Application for plugging approved 6-25 19 64

Plugging commenced 7-8 19 64


Plugging completed 7-11 19 64

Reason for abandonment of well or producing formation

Depletion of all producible formation.

If a producing well is abandoned, date of last production 6-4- 19 64

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Mississippi Depth to top 4168 Bottom 4232 Total Depth of Well 11180 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Water and small amount of gas	4172	4183	8-5/8"	282'	None
				4-1/2"	4300'	3936.99'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 4160! Mixed and ran 3 sacks cement thru dump bailer. Mudded hole to 300' followed by a 10' rock bridge. Mixed and ran 25 sacks cement thru dump bailer. Mudded hole to 40', followed by a 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1964

7-16-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Monte Chadd (employee of owner) or (conservation operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Monte Chadd, Dist. Prod.

(Signature) *Monte Chadd*

Route 2, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1964

My commission expires September 23, 1967

Samuel J. ...
Notary Public.

WELL LOG

15-095-00259-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 33 T. 29S R. 9W

FARM BOHRER "B" NO. 1

LOC. NE, NE, SE


TOTAL DEPTH 4480'

COUNTY Kingman Co., Kansas

COMM. June 29, 1957

COMP. July 15, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 280' W/200 sax.
4 1/2" @ 4300' W/100 sax.

ELEVATION 1585' DF

PRODUCTION Mississippian

FIGURES INDICATE BOTTOM OF FORMATIONS

35	Surface sand
60	Gravel & sand
70	Blud shale
130	Red bed
282	Red bed & red rock
720	Red bed & shale
1328	Shale & shells
1361	Anhydrite
1445	Lime & shale
1575	Lime
2625	Shale & lime
2655	Lime
2990	Shale & lime
3149	Lime
3345	Lime & shale
3495	Sand & shale
3987	Lime
4044	Lime & shale
4095	Lime
4166	Lime & shale
4196	Chert
4235	Lime & chert
4242	Lime
4284	Lime & shale
4300	Lime
4466	Shale
4480	Lime & shale
4480	T. D.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Bohrer "B" well

Subscribed and sworn to before me this 5th day of August 19 57

My Commission Expires: July 11, 1960

Verne A. Morris
Zed T. Brown
NOTARY PUBLIC