

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 30 TWP. 29 RGE 9 E/W
Location as in quarters or footage from lines:
SE SE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Western Drilling of Arizona
Lease Name LESLIE Well No. 1
Office Address 7375 East 5th Ave. Scottsdale, Arizona 85251
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed 10-18-82
Application for plugging filed 10-18-82
Plugging commenced 10-19-82
Plugging completed 10-19-82
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 4414
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Bottom Plug: @ 260' w/35 sacks common cement 2% cc thru drill pipe
Top Plug: @ 60' w/20 sacks " " "
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.
Ervin Neighbors (~~employee of owner~~) or ~~XXXXXX~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
Box 877 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of October 19 82

Deborah RECEIVED
STATE CORPORATION COMMISSION Public.

My Commission expires: 4-29-86

OCT 26 1982

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: October 11, 1982
DATE COMPLETED: October 19, 1982

Western Drilling of Arizona
LESLIE #1
SE SE NE
Sec. 30, T29S, R9W
Kingman County, Ks.

ELEVATION:

0 - 2434' Surface Soil, Sand
2434 - 3382' Sand, Shale
3382 - 3587' Shale & Lime
3587 - 4196' Lime
4196 - 4398' Shale & Lime
4398 - 4414' Chert, Lime
4414' RTD

FORMATION DATA

Indian Cave 2434'
Heebner 3382'
Douglas 3413'
Lansing K.C. 3587'
Base K.C. 4196'
Mississippi 4210'
Kinderhook 4225'
Viola 4398'
RTD 4414'

Surface Pipe: Set new 8-5/8"
20# pipe @246' w/225 sacks
60/40 pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

E. Neighbors

Subscribed and sworn to before me this 25 day of October 1982.

My Comm. Expires:
4-29-86

Dorothy M. Sigwe
Notary Public

RECEIVED
STATE COMMISSION

OCT 26 1982

CONSERVATION DIVISION
Wichita Kansas