


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 30 Twp. 29 Rge. 9 (E) W (W)



Location as "NE/CNWxSWx" or footage from lines NE SE
Lease Owner Morganstern & Specter, Inc.
Lease Name Leslie Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-8-63 _____ 19____
Plugging completed: 1-17-63 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4522 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	408'	None
				5-1/2"	4518'	3253'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4242', sanded to 4175' and dumped 5 sacks of cement @ 4175' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 200', set rock bridge to 190' and ran 20 sacks of cement @ 190'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

JAN 23 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January, 1963

My commission expires May 20, 1964 Milton J. Tolin Notary Public.




WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company: CITIES SERVICE OIL CO.
Farm: Leslic No. 1

SEC. 30 T. 29 R. 9W
C NE SE
660' S & 660' W of E/4c

Total Depth. 4484 PBD 4471
Comm. 7-3-56 Comp. 7-19-56
Shot or Treated. Perf. 41/4391-4401, 500 gal acid
Contractor. Barbour Drilling Co.
Issued. 9-15-56

County Kingman
KANSAS



Elevation. 1659 DE

Production. 16,900,000 CFGPD

CASING:

8 5/8 @ 406' w/ 250 sx cmt.
5 1/2 @ 4484' w/ 150 sx cmt.

Figures indicate Bottom of Formations

shale & shells	180
red rock	1595
lime & shale	1730
lime	1855
lime & shale	2045
lime	2455
shale & lime	3015
lime	3125
lime & shale	3240
lime	3345
lime & shale	3480
sand & shale	3568
lime	4213
lime & chert	4235
shale & lime	4341
shale	4390
shale & lime	4406
lime	4470
shale & sand	4483
sand	4490
SLM	4484
Total Depth	
Plugged back to	4471
TOPS: (Corrected)	
Lansing	3574
Mississippi	4188
Kinderhook	4213
Viola	4390
Simpson	4459
Simpson sand	4469
Penetration	15

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1963
CONSERVATION DIVISION
Wichita, Kansas