

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238. - Logs submitted

LICENSE # 5153 EXPIRATION DATE June 30, 1983 prior to completion of

OPERATOR Texaco Inc. API NO. 15-035-23,136 well

ADDRESS P.O. Box 2420 COUNTY Cowley

Tulsa, OK 74102 FIELD Estep

** CONTACT PERSON B. A. Batson PROD. FORMATION Stalnaker

PHONE 743-5311

PURCHASER Farmland Industries Inc. LEASE C. W. Estep

ADDRESS RFD #4 WELL NO. 3

Winfield, KS 67156 WELL LOCATION C SE SW SE

DRILLING Reynolds Drilling Co. 1750 Ft. from East Line and

CONTRACTOR 0201 College 330 Ft. from South Line of

ADDRESS Winfield, KS 67156 the SE (Qtr.) SEC 21 TWP 34S RGE 6E

PLUGGING None WELL PLAT (Office Use Only)

CONTRACTOR ADDRESS

ADDRESS

TOTAL DEPTH 1865' PBTB 1817'

SPUD DATE 6-23-82 DATE COMPLETED 7-28-82

ELEV: GR 1323' DF KB 1327'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 8-5/8" @ DV Tool Used?

THIS AFFIDAVIT APPLIES TO: (Circle ONE) Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO, Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

B. A. Batson, being of lawful age, hereby certifies

that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

B. A. Batson Asst. Dist. Mgr. (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 5th day of August 1982.

MY COMMISSION EXPIRES: January 26, 1983

(NOTARY PUBLIC)

** The person who can be reached by phone regarding any questions or information.

RECEIVED STATE CORPORATION COMMISSION OCT 27 1983 CONSERVATION DIVISION Wichita, Kansas

10-27-83

OPERATOR Texaco Inc. LEASE C. W. Estep #3 SEC. 21 TWP. 34S RGE. 6E

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red Bed & Sand	0	479	Dual Ind. Lat. Log	1865-479'
Shale	479	650	GR-FDL	1865-479'
Lime & Shale	650	1565		
Lime	1565	1865		

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (In O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	14#	479	50-50 Poz Class A	200 150	3% CC
Production	7-7/8"	5-1/2"	14#	1865'	50-50 Poz	90	10% Salt & 75% CER-2

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	1/2"	1796-1800'

TUBING RECORD		
Size	Setting depth	Packer set at
2-3/8"	1793'	1770'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
300 gal 15% NEA	1796-1800'

Date of first production 7-10-82	Producing method (flowing, pumping, gas lift, etc.) Pump & gas	Gravity 350 @ API
RATE OF PRODUCTION PER 24 HOURS	Oil 1 bbls.	Gas Tr gas
Disposition of gas (vented, used on lease or sold)		Gas-oil ratio 1796-1800

RECEIVED
OCT 27 1983
CONSERVATION DIVISION
Wichita, Kansas