

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) - KCC# (316) 263-3238.

LICENSE # 5587 EXPIRATION DATE 6-30-83

OPERATOR Watson Petroleum API NO. 15-035-23140-0000

ADDRESS 403 N Hillcrest COUNTY Cowley

Wichita Kans 67208 FIELD Estep

** CONTACT PERSON L.A. Watson PHONE 682-7131 PROD. FORMATION Stalnaker Sand

PURCHASER None LEASE Kubik

ADDRESS WELL NO. 2

DRILLING White & Ellis Drilling Ft. from Line and

CONTRACTOR ADDRESS Box 448 Ft. from Line of

El Dorado, Kansas 67042 the SE (Qtr.) SEC 28 TWP 34 RGE 6E.

PLUGGING None WELL PLAT (Office Use Only)

CONTRACTOR ADDRESS

TOTAL DEPTH 3137 PBTD

SPUD DATE 8-3-82 DATE COMPLETED Uncompleted

ELEV: GR NA DF KB

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE No. Prod.

Amount of surface pipe set and cemented 312 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO, Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

AFFIDAVIT

L.A. Watson, being of lawful age, hereby certifies

that: I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

[Signature]

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 30 day of December

1982.



MY COMMISSION EXPIRES:

[Signature] (NOTARY PUBLIC)

** The person who can be reached by phone regarding any questions concerning this information.

RECEIVED STATE CORPORATION COMMISSION

OCT 19 1983

CONSERVATION DIVISION WICHITA

10-19-83

OPERATOR Watson Petroleum, Inc. LEASE Kubik SEC. 28 TWP. 34 SRGE. 6E

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 2

FORMATION DESCRIPTION; CONTENTS, ETC.			TOP	BOTTOM	NAME	DEPTH
<p>Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.</p> <p>XXX Check if no Drill Stem Tests Run.</p>						
<p>Bridge Plug Set at 2850</p>						
<p>If additional space is needed use Page 2, Side 2</p>						

Report of all strings set — surface, intermediates, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Seals	Type and percent additives
Surface		8 5/8		312	Common	170	3% C.C.
Production		4 1/2		3135	Common	150	


LINER RECORD			PERFORATION RECORD			
Top, ft.	Bottom, ft.	Seals cement	Shots per ft.	Size & type	Depth interval	
None			4	DP 3 1/8	3112-13	3115-17
			4		2772-75	
TUBING RECORD						
Size	Setting depth	Packer set at				
None						

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal. 10% mud acid, 750 gal. 15% NE acid	3112-17
500 gal. 10% Reg. acid	2772-75

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
None		
Estimated Production - I.P.	Oil	Gas
	bbbls	MCF
Perforations	Water %	Gas-oil ratio
	bbbls	CFPS

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1983
CONSERVATION DIVISION
Wichita, Kansas



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Watson Petroleum, Inc. 403 N. Hillcrest, Wichita, Ks. 67208

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Kubik Well No. #2

Sec. 28 T. 34S R. 6E Spot NE NW SE

County Cowley State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 312.2' with 170 sx. 3%cc.

Production: 4 1/2" @ 3135' with 150 sx.

Type Well: Oil Total Depth 3137'

Drilling Commenced 8-3-82 Drilling Completed 8-10-82

Formation	From	To	Tops
Collar	0	7	Layton 2260
Shale, Lime	7	1756	Mississippi 3103
Lime	1756	1762	
Shale	1762	1777	
Sand	1777	1838	
Shale	1838	1950	
Sand	1950	1982	
Sand, Shale	1982	2030	
Shale	2030	2088	
Shale, Lime	2088	2141	
Shale, Lime	2141	2260	
Sand	2260	2397	
Shale, Lime	2397	2690	
Lime	2690	2744	
Shale	2744	2766	
Lime	2766	2790	
Shale, Lime	2790	2849	
Lime, Shale	2849	2901	
Shale, Lime	2901	2919	
Lime, Shale	2919	2930	
Sand	2930	2938	
Shale	2938	3103	
Lime	3103	3137	