

15-095-01556-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Kingman County. Sec. 35 Twp. 29S Rge. (E) 7 (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NW



Locate well correctly on above  
Section Plat

Lease Owner O. A. Sutton  
Lease Name Voran Well No. 1  
Office Address 800 Sutton Place, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed November 18 1958  
Application for plugging filed July 3 1969  
Application for plugging approved July 8 1969  
Plugging commenced July 15 1969  
Plugging completed July 17 1969  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production July 1 1969  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren  
Producing formation Mississippi Depth to top 4112 Bottom \_\_\_\_\_ Total Depth of Well 4260 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	264'	
				5 1/2"	4259'	3100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pulled 43 joints 5 1/2" casing (3100' total). Mud to 240'. 10-foot rock bridge to 230'. Dumped 3 1/2 yards cement to surface. Job complete 7-17-69.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.  
Address 320 North Park, Stafford, Kansas 67578

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jack G. Paulsen (employee of owner) or ~~(owner or operator)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen  
Jack G. Paulsen  
800 Sutton Place, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of August, 1969.

My commission expires June 28, 1970.  
Jean S. Taylor Notary Public.

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

H. W. VORAN #1  
NW NW NW SECTION 35-29-7W  
KINGMAN COUNTY, KANSAS

COMMENCED 11-5-58  
COMPLETED 11-18-58

DEPTH		FORMATION	
FROM	TO		
0	265	SHALE & SHELLS	RAN 265' OF 8 5/8" CASING, CEMENTED WITH 200 SACKS CEMENT.
265	900	SHALE & SHELLS	
900	1250	ANHYDRITE & SHALE	
1250	1640	LIME & SHALE	
1640	1700	LIME	
1700	1880	LIME & SHALE	
1880	2055	SHALE & SHELLS	
2055	2265	SHALE & LIME	
2265	2455	SHALE & SHELLS	
2455	2900	LIME & SHALE	
2900	3198	LIME	
3198	3270	SAND	
3270	3295	SAND & SHALE	
3295	4015	LIME	
4015	4125	LIME & SHALE	
4125	4145	LIME	
4145	4195	LIME & CHERT	
4195	4260	LIME	
4260	TD		RAN 138 JOINTS OF 5 1/2" CASING CEMENTED WITH 200 SACKS CEMENT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 7 1969  
CONSERVATION DIVISION  
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE H. W. VORAN #1 WELL.

*E. E. Hall*

STATE OF KANSAS )  
                          )     ss  
COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 24TH DAY OF NOVEMBER, 1958 PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES September 3 1962 *Catherine L. L...*  
NOTARY PUBLIC