

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-20568-0000

LEASE NAME Kostner

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Martin Oil Producers, Inc.

SEC. 3 TWP. 29 RGE. 6 ~~N~~ or (W)

ADDRESS 150 N. Main, #1010, Wichita, KS 67202 COUNTY Kingman

PHONE# (316) 264-0352 OPERATORS LICENSE NO. 5097 Date Well Completed 5/27/77

Character of Well oil Plugging Commenced 4/19/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 4/22/96

The plugging proposal was approved on 4/10/96 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4040 Bottom 4078 T.D. 4078

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	oil/gas/water	4040	4078	8 5/8 4 1/2	241 4074	0 3420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. A CIBP was set at 4012' & capped with 2 sacks cement. The pipe was shot loose at 3420' & pulled to 1060' where 35 sacks cement spotted, 4 1/2" pulled to 837' and 35 sacks cement spotted & 4 sacks hulls. Pulled 4 1/2" to 335' & circulated cement to surface. Pulled all 4 1/2" & topped off hole. Used 192 sacks 60-40
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dewey Gressel License No. 30375

Address 2029 N. B Street, Wellington, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Martin Oil Producers, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. S. Martin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 150 N. Main, #1010
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 96

[Signature]
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 07 1996
5-7-1996

CONSERVATION DIVISION
WICHITA, KS Commission Expires:



Pozmix, 11 sacks gel, 200# cotton seed hulls.

