


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

KINGMAN County, Sec. 21 Twp. 29S Rge. 6W (#) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner PETROLEUM, INC.  
Lease Name MATSON Well No. 1  
Office Address ROUTE 2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JULY 20 19 60  
Application for plugging filed JULY 20 19 60  
Application for plugging approved JULY 20 19 60  
Plugging commenced JULY 20 19 60  
Plugging completed JULY 20 19 60  
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRID HAMEL, PRETTY PRAIRIE, KANSAS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4227' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 240', FOLLOWED BY WOODEN PLUG AND 1/4 SACK HULLS. PLACED 15 SACKS CEMENT THROUGH DRILL PIPE ON TOP OF PLUG. MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG AND 1/4 SACK HULLS. PLACED 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 1960 8-4-1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (agent) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 1ST day of AUGUST, 19 60

My commission expires APRIL 14, 1963

Arthur J. Wiles  
Notary Public.



# WELL LOG

15-095-00137-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 21 T29S R. 6W

FARM MATSON NO. 1

LOC. Approx. NW, NW, NW


TOTAL DEPTH 4227'

COUNTY KINGMAN CO., KANSAS

COMM. July 9, 1960

COMP. July 20, 1960

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 255' w/200 sax.

ELEVATION 1579' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

80	Sand, clay & gravel
440	Red bed
1045	Red rock & shale
1260	Lime & shale
1490	Lime
1895	Lime & shale
2885	Shale & lime streaks
3060	Lime & shale
3173	Shale & lime
3577	Lime & shale
3708	Lime
3745	Lime & shale
4050	Lime
4153	Lime & shale
4227	Mississippi
4227	T. D.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 1960

CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS }  
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 MATSON well

*Verne A. Morris*

Subscribed and sworn to before me this 28th day of July 19 60

My Commission Expires: April 14, 1963

*Arthur J. Miles*  
NOTARY PUBLIC